



GOVERNMENT OF WEST BENGAL
OFFICE OF THE SUPERINTENDENT
TUFANGANJ S.D HOSPITAL
Tufanganj, Cooch Behar

Memo No.599/21

QUOTATION NOTICE

Dated 24.08.21

Sealed quotation is hereby invited from reputed firm/ agency/Dealer/Distributor, for the supply and Installation of the following for Telemedicine Department of Tufanganj S.D Hospital Interested agencies are requested to submit their rate for the supply of the following along with supporting document as per the NIQ within **31.08.21 up to 1 P.M.** The quotation will be opened on 31.08.21 2 P.M

1. Trade License-Up to Date
2. GST Registration
3. Xerox of PAN

Terms & Condition

01. The Willing Agencies/Party/ are advised to submit their rate per unit by his own letter Head favour of SUPERINTENDENT_TUFANGANJ S.D HOSPITAL with quotation.

02. The Rate should be clearly mentioned including GST for the supply and Installation of item mentioned below in figure and words no overwriting or cutting is permitted in the Bid Document.

03. The Undersigned reserves the right to accept or reject any quotation/tender without assigning any reason.

Details are given below

S/N	Name of the item	Quantity
01.	<u>Delivery & Installation</u> of BEE 3 Star rated,230V,1.5 ton inverter split type air conditioner(Non-Inverter ,R-32 or 410A)having nominal cooling capacity-5120 watt(1.5 ton),Maximum Power consumption (Watt)2650 Watt(CBU-I IDU+1 ODU)(Make: Mitsubishi Electric Model or Equivalent make of OGENERAL	01 No.
02.	Necessary Electrical Works for installation of A.C as per Specification enclosed herewith.	01 Work

Enclose Details of Specification



(Dr.M.K Adhikari)
Superintendent
Tufanganj S.D Hospital
Cooch Behar

Dated 24.08.21


Memo.599/ 1(6)/21

Copy forwarded for information and publishing to:

01. The Sub-divisional Officer, Tufanganj for wide circulation
02. The Chairman Tufanganj Municipality
03. The Assistant Chief Medical Officer of Health, Cooch Behar.
04. Notice board of this office.
05. The DIO NIC Cooch Behar request to upload NIQ to Coochbehar.gov.in
06. The SAE PWD Electrical Tufanganj.


(Dr.M.K Adhikari)
Superintendent
Tufanganj S.D Hospital
Cooch Behar

Sl. No.	DESCRIPTION OF WORKS	Qty	Unit
SUB-HEAD 1-DISTRIBUTION WIRING			
1	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Make- Polycab / Havells / Finolex / KEI) in 20mm size PVC rigid conduit 'FR' HMS / MMS type with same make of fittings e.g. Tee / bend / L joints / saddle etc (Make Precision / Polycab), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switch (Anchor make) fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size "Ph & N" copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish	16	mtr
a)	2x84/0.3 (6 sqmm) + 1x56/0.3 (4 sqmm) as ECC		
2	Supply & Fixing 240 V, 25 A, 3 pin Modular type plug top with indicator (Make- Legrand-Arteor / Schneider- Zencelo / Crabtree - Murano / L & T- Englaze) & necy. Connections.	1	Set
3	Supply & Fixing 240 V, 25 A, Modular type starter (Make- Legrand-Arteor / Schneider- Zencelo / Crabtree - Murano / L & T- Englaze) with 2 Module GI Modular type switch board with 2 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	1	Set
SUB-HEAD 2--- SITC OF SPLIT AC			
4	Supply & Delivery of BEE 3 star rated, 230V, 1.5 ton no inverter split type air conditioner (Non-Inverter, R-32 or R-410A) having nominal cooling capacity-5120 watt (1.5 ton), Maximum power consumption (Watt) 2650 Watt (CBU-1 IDU +1 ODU) (Make:-Mitsubishi Electric Model or equivalent make of OGENERAL)	1	no
5	Installation, testing & commissioning of 1.8/2.2/2/1 ton AC machines complete with outdoor condensing unit on iron angle / powder coated brackett & indoor cooling unit on wall with suitable brackett . Rate is inclusive of cutting of wall for making holes and mending good the damages.	1	no
6	Supply and drawing 5/8" & 1/4" copper refrigerant pipes with 9 mm thick rubber nitrile rubber insulation along with other accessories on the surface of wall	5	mt
7	Supply and drawing copper communication & controlling cable of following size-- 4 Core x 2.5 sq.mm copper cable (Make: Finolex / KEI / Polycab / Havells)	5	mt



 Superintendent
 S.D. Hospital
 Cooch Behar, Pin-786109